## 646 S. CALIFORNIA ST. STOCKTON, CA 95203

PHONE: (209)466-9625 FAX: (209)466-1324

## **QUOTE # 1479**

CUSTOMER: City of Stockton DATE September 1, 2021

CONTACT

**PHONE** 937-5422

OB SITE  Quantity	Sewer Pump  24" - two stage propeller pump	TOTAL AMT.	
		1017	<u> </u>
	LABOR Sanitize pump, disassemble pump, clean and inspect column, measure and inspect all parts,		
	cut, machine and thread new head shaft, tube line and shaft, remove packing box bearing, machine new		
	bearing, press new bearing into packing box, weld centering spider to pump column, grease pack tube		
	line, assemble pump, apply two part epoxy to outside of column	\$	16,048.0
	Sandblast Fee outside of pump column	\$	3,000.0
	Waste Fee	\$	37.5
	MATERIAL		
1	Bowl assembly model # A59M22 two stage	\$	46,027.0
1	Material to fabricate centering spiders	\$	300.0
30'	Tube line and shaft, 4" x 2 -7/16" using stainless steel shafts	\$	7,500.0
1	Lot two part epoxy	\$	1,200.0
1	MSCL painting supplies, metal etch, acetone, bushes and rollers	\$	300.0
1	Packing box bearing and packing	\$	125.
1	MSCL material	\$	150.
1	Lot stainless steel bolts and nuts	\$	400.
1	Disinfection material	\$	100.0
1	Grease pack tube line	\$	200.0
	NOTE Delta Pump Co. is not responsible for existing material condition		
	Additional time and material may be needed to complete job		
	Quote valid for 30 days  Material	\$	56,302.
	Payment Terms - 2 % 10 - NET 15 Sales Tax 9.00%	\$	5,067.
	( discount \$ 1,625.09 if paid by 10th day ) After invoice date Labor	\$	19,085.5
	For balances past due, the 31th day, a 1.5% late fee will be Freight Charge	\$	800.0
	added and applied every 30 days thereafter		
	No warranty on electrical equipment Total	\$	81,254.